

BILL OF QUANTITIES - MEASURED ITEMS (REVISED)					
No.	ITEM	UNIT	QTY	RATE Rs	AMOUNT Rs
PART I - SURVEY, SITE CLEARANCE & EXCAVATION		4 ITEMS	Rs 19,12,726		
1	Confirmatory Soil & Rock Core Boreholes	No	4	50000	2,34,660
2	Site Clearance, Grubbing & Setting Out	Sqm	1800	44.8	96,500
3	Mass Excavation in Basalt / Murum (~6.8 m)	Cum	1539	850	15,12,570
4	Surface Dressing & Anti-Termite Treatment	Sqm	320	180	68,996
PART II - SUBSTRUCTURE & FOUNDATION WORKS		5 ITEMS	Rs 12,83,471		
1	Formwork for Mat Raft & Bay 5 Sump	Sqm	125	410	82,750
2	PCC 1:3:6 Levelling Bed (100 mm)	Cum	17.17	5500	1,05,831
3	Monolithic Mat Raft Casting (M35)	Cum	81.84	8640	7,62,082
4	Pre-Applied Waterproofing Membrane + Screed	Sqm	280	950	2,80,832
5	Dual Swelling Hydrophilic Kicker Waterstops	M	68	650	51,976
PART III - SUPERSTRUCTURE & STRUCTURAL RCC		11 ITEMS	Rs 41,45,877		
1	Formwork for 600 mm Shear Walls (3.2 m Ht)	Sqm	480	580	4,11,888
2	Casting 600 mm Perimeter & Shear Walls (M35)	Cum	132.61	8640	12,36,918
3	Formwork & Staging for 900 mm Pressure Slab	Sqm	145	650	2,16,650
4	Casting 900 mm Pressure Roof Slab (M35)	Cum	114.72	8640	10,73,657
5	Internal Dog-Leg Staircase RCC	Cum	4.8	9200	58,992
6	Headhouse Structure (400 mm Wall / 500 mm Roof)	Cum	28.56	8640	2,80,130
7	Approach Stairwell RC Box (250 mm RC)	Cum	18.2	8640	1,75,788
8	Engineered burster slab (200 mm M30 — RC1 R-1, was 300 mm ...	Cum	38.4	8200	3,40,140
9	Sentry post RC frame — brick infill measured as brickwork ...	Cum	18.6	8500	1,87,764
10	110 mm Internal Brick Partition Walls	Sqm	95	920	1,09,648
11	Escape shaft collars ESC 1 and ESC 2, 250 RC, OD 1900 — ADDED ...	Cum	6.285	8640	54,302
PART IV - REINFORCEMENT STEEL & SHIELDING		7 ITEMS	Rs 63,33,152		
1	Pressure Roof Slab Rebar (T25 / T12)	Tonne	23.22	78000	20,11,392
2	Perimeter & Shear Wall Rebar (T16 / T20)	Tonne	17.85	78000	15,70,284
3	Mat Raft & Haunch Diagonal Rebar	Tonne	13.14	78000	11,36,160
4	Headhouse, Approach & Staircase Steel	Tonne	6.76	78000	6,01,440
5	Burster Slab Mesh (T12 @ 150 B/W) [REVIEW — RC1 R-12: T12 @ ...	Tonne	2.89	78000	2,58,792
6	Sentry Post Structural Rebar	Tonne	3.93	78000	3,36,204
7	EMP Welding at 4th Node & Bonding Straps	Item	1	380000	4,18,880
PART V - CBRN, EMP, CLOSURES & ANCILLARY SERVICES		11 ITEMS	Rs 1,05,45,028		
1	Blast Doors 1 & 2 (≥7 bar, Rebound-Rated)	Set	2	1250000	25,50,400
2	Emergency Exit Hatches (900 mm Clear, 621 kPa)	Set	2	450000	9,22,248
3	Fast-Acting Blast Valves BV-1 to BV-3 (DN100)	Set	3	160000	4,90,368
4	Generator Blast Valves BV-4 & BV-5 (DN350)	Set	2	320000	6,50,368
5	NBC Collective Protection Trains (2 × 300 m³/h)	Set	2	1850000	37,72,576
6	Sealed Zone-2 Welded EMP Enclosure (3×3×2.4 m)	Item	1	850000	8,94,496
7	Layerwise Engineered Fill & Basalt Rubble Berm	Cum	620	420	3,42,168
8	Submersible Sump Pumps + Effluent Piping + Septic	Set	1	420000	4,56,500
9	Sand-Faced Internal Plaster, Punning & Painting	Sqm	720	180	1,99,632
10	Testing, Commissioning & Envelope Leakage Test	Item	1	250000	2,66,272
11	Standby generator 15 kVA in Bay 8, with fuel system, exhaust ...	Set	1	-	NOT PRICED

MASTER CONSTRUCTION PROGRAMME				
ID	ACTIVITY	DAYS	START	FINISH
1	MASTER CONSTRUCTION SCHEDULE	224	02-11-26	26-07-27
2	Initial Works	4	02-11-26	05-11-26
6	Substructure Works	40	02-11-26	18-12-26
11	Center Line Works	4	14-11-26	18-11-26
14	Monolithic Mat Raft, 600mm Thk Periphery Shear Wall RC	20	19-11-26	11-12-26
27	Superstructure RCC Works & Brick Works	82	19-12-26	26-03-27
28	1st Slab (900 mm Thk) RCC Works (DECN Room, Gen Room R	25	19-12-26	16-01-27
42	2nd Slab (Ground Lvl) - Grade Slab RCC Works	23	18-01-27	13-02-27
52	2m Engineered Cover Grade Slab RCC Works	4	10-02-27	13-02-27
55	3rd Slab (First Floor Slab) RCC Works	10	15-02-27	25-02-27
68	4th Slab (Headhouse Roof Slab) RCC Works	10	26-02-27	09-03-27
81	RCC Slab Deshuttering,Cleaning & Housekeeping Works	32	17-02-27	26-03-27
86	Finishing Works	112	16-03-27	26-07-27
87	Brickworks	12	16-03-27	29-03-27
92	Internal Sand Faced Plaster	18	20-03-27	09-04-27
99	External Plaster - Scaffold Erection, Thiyya, 1st & 2n	8	29-04-27	08-05-27
112	Door Works	8	05-06-27	14-06-27
125	Internal Paint Final (2nd) Coat	6	09-07-27	15-07-27

COST SUMMARY		
COST HEAD	BASIS	AMOUNT Rs
Total Basic Cost	Subtotal Packages	2,42,20,254
Contingencies	3.0%	7,26,608
Water & Electricity Provisions	1.0%	2,42,203
Specialist CBRN / EMP & Engineering Consultant	6.0%	14,53,215
Site Supervision & Quality Assurance	2.0%	4,84,405
Statutory Clearances & Liaisoning	1.0%	2,42,203
Contractor's Overhead & Profit	10.0%	24,22,025
FINAL PROJECT COST	-	2,97,90,913

BILL OF QUANTITIES - PART SUMMARY			
PART	DESCRIPTION	ITEMS	AMOUNT Rs
I	SURVEY, SITE CLEARANCE & EXCAVATION	4	19,12,726
II	SUBSTRUCTURE & FOUNDATION WORKS	5	12,83,471
III	SUPERSTRUCTURE & STRUCTURAL RCC	11	41,45,877
IV	REINFORCEMENT STEEL & SHIELDING	7	63,33,152
V	CBRN, EMP, CLOSURES & ANCILLARY SERVICES	11	1,05,45,028

WHAT THE REVISED BILL CARRIES			
ITEM	AS MEASURED	QUANTITY	NOTES
BURSTER SLAB	200 THK M30	38.40 m3	REDUCED FROM 300 THK M35 AND 57.60 m3
SENTRY POST	RC FRAME ONLY	-	THE BRICK INFILL IS MEASURED SEPARATELY AS BRICKWORK
ESCAPE SHAFT COLLARS	250 RC, OD 1900	6.285 m3	ADDED AS A MEASURED LINE
GENERATOR	15 kVA	1 No.	ADDED AS A VISIBLE LINE
CONCRETE TOTAL	-	467.59 m3	= THE SUM OF ITS OWN LINES
PROGRAMME WORDING	13 ACTIVITIES	-	2.0 m COVER, 900 SLAB AND THE POST-M1 BOX SIZE

UNDERGROUND CBRN-HARDENED BLAST-RESISTANT PROTECTIVE STRUCTURE + SENTRY POST PUNE, MAHARASHTRA	
NOTES	
1.	ALL AMOUNTS ARE IN INDIAN RUPEES. ALL DURATIONS ARE IN WORKING DAYS. ALL DATES ARE dd-mm-yy.
2.	WRITTEN FIGURES TO BE FOLLOWED ONLY.
3.	THIS DRG IS TO BE READ IN CONJUNCTION WITH THE FULL BILL OF QUANTITIES. THE COST ESTIMATE AND THE MASTER CONSTRUCTION SCHEDULE.
4.	FINAL PROJECT COST Rs 2,97,90,913, BUILT UP FROM A TOTAL BASIC COST OF Rs 2,42,20,254 IN 38 MEASURED ITEMS UNDER FIVE PARTS.
5.	MASTER CONSTRUCTION PROGRAMME 224 DAYS, 02-11-26 TO 26-07-27, IN FOUR PHASES: INITIAL WORKS, SUBSTRUCTURE, SUPERSTRUCTURE AND FINISHING. THE PROGRAMME TABLE LISTS THE SUMMARY ACTIVITIES; THE FULL SCHEDULE CARRIES 130.
6.	THE BURSTER SLAB IS 200 THK M30 AND 38.40 CUM. THE SENTRY POST IS MEASURED AS AN RC FRAME WITH ITS BRICK INFILL MEASURED SEPARATELY AS BRICKWORK.
7.	THE TWO ESCAPE SHAFT COLLARS, 250 RC AT OD 1900, ARE MEASURED AS A LINE AT 6.285 CUM, AND THE 15 kVA GENERATOR IS A VISIBLE LINE.
8.	THE CONCRETE TOTAL IS 467.59 CUM, WHICH IS THE SUM OF ITS OWN LINES.
9.	AMOUNTS AND RATES ARE THE BILL'S OWN. A LINE SHOWN NOT PRICED CARRIES NO RATE IN THE BILL AND IS NOT INCLUDED IN ANY TOTAL ON THIS SHEET.
10.	ITEM DESCRIPTIONS ARE THE BILL'S OWN, TRIMMED TO THE COLUMN WHERE MARKED WITH AN ELLIPSIS. THE BILL GOVERNS.
11.	CONTRACTOR TO CHECK AND VERIFY THE FIGURES BEFORE TENDER.
WORKS MANAGEMENT - MASTER PROGRAMME AND BILL OF QUANTITIES	
CBRN HARDENED UG OPS ROOM	
SHEET 13	
Project number	01
Date	18 SEP 2026
Drawn by	SYN 01
Checked by	DR IR CHAUDHARI
WMS013	
Scale	Not to scale